
RL40BP

4.0 TON 2 POST BASE PLATE HOIST

REDLINE HOIST

Ph: 04 777 HOIST

Ph: 04 777 46489




FEATURES:


1. CE certified and Australian Design Registered
2. Column reinforced bending with 6 bends
3. Structural Integral carriage design
4. Ground cover plate for hardware protection
5. Anti-fall valve installed on hydraulic system
6. Hydraulic cylinder with two pressure seals per cylinder
7. Quality power unit for safe and reliable operation
8. Set of (4) 70mm and 100mm lift adapters
9. CE certified and Australian Design Registered


TECHNICAL SPECIFICATION


Lifting Capacity	4000kg	Lifting time	45 - 50 sec
Max Lifting height	1820mm	Motor voltage	1ph-240V / 3ph-415V
Minimum height	100mm	Motor power	2.2KW
Overall height	2680 Column / 3140mm Carriage	Min Concrete Requirement	110mm or 125mm / 32mpa
Overall width	3486mm	Freight Dimensions	2880 x 550 x 730 / 650kg



Column with structural 6 bend system


Structural integral carriage design



Diamond plate cover to protect all hardware


Anti rotation structure at cylinder pulley with heavy duty chain


Cable pulley made from heat treated steel


Safe and reliable geared arm restraints


Hydraulic cylinder designed and tested with two pressure seals


Steel pulley with easy lubrication system


Set of (4) double screw round lift pad


Set of (8) 70mm/100mmeffective height lift pad extensions



BASEPLATE EXTENSION OPTION AVAILABLE

www.redlinehoist.com.au

RL40BP

REDLINE HOIST

